KADUR FOREST DIVISION.

Abstract Notification dated the 14th September 1936.

The attention of the public is invited to the detailed notification, calling for tenders up to 4 P.M. on the 2nd October 1936, for the collection and carting of rough sandalwood from the several Ranges of Kadur Division to Chikmagalur Koti, during 1936-37, published on pages 1526-1527, Part VI of the *Mysore Gazette*, dated 24th September 1936.

Abstrast Notification dated 15th September 1936.

The attention of the public is invited to the detailed notification regarding the sale of the right to prepare and remove timber from trees cut in the plantations areas of the State Forests in this Division during 1936-37, published on pages 1524-1525, Part VI of the *Mysore Gazete*, dated 24th September 1936.

Abstract Notification dated the 17th September 1936.

The attention of the public is invited to the detailed notification, regarding the sale of the right of cutting and removing timber from the several coupes of this Division, during 1936-37, published on pages 1527-1528, Part VI of the *Mysore Gazette*, dated 24th September 1936.

M. A. MUTHANNA,
District Forest Officer.

ENGINEERING DEPARTMENT

BUREAU OF SANITARY ENGINEERING.

Abstract Notification dated 14th September 1936.

The attention of the public is invited to the Notice, dated 10th September 1936, calling for tenders for the work of Sanitary Installation with drainage arrangements to Sri Narasimharaja Hospital, Kolar, published on pages 1517 and 1518 of Part VI of the *Mysore Gazette*, dated 17th September 1936.

The last date for receipt of tenders will be 2nd October 1936.

B. R. GARUDACHAR,
Sanitary Engineer.

BUILDINGS DIVISION, BANGALORE.

Notification dated 28th September 1936.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Buildings Division, up to 12th October 1936, for Constructing the Kannada Boys' School at Mamoolpet, Bangalore City. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of January 1937.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Buildings Division, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rupees one thousand and six hundred only in cash or Government promissory notes, as earnest money, and be superscribed "Tender for Constructing the Kannada Boys' Middle School at Mamoolpet, Bangalore City" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office, in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for Contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

13. Transfer of works to third parties by selected contracter will not be countenanced by the Department and in the case of any such attempt, the earnest money is liable to be forfeited at the discretion of the Chief Engineer.

Abstract estimate of the quantities for Constructing the Kannada Boys' Middle School at Mamoolpet, Bangalore City.

No.	Items of work	Per	Rate	Quantity	Rate to be quoted
	Ground Floor.		Rs. a. p.		
1	Earthwork excavation for foundation and filling in basement including working and tamping, etc.	C.yds.	0 3 0	452	
2	Concrete stone jelly in lime mortar 1 : 2 : 4 in layers of 6″ including tamping, etc., ..	C.ft.	0 3 6	3,084	
3	Sized stone in lime mortar 1 : 2 in foundation and basement with bond stones 6′ apart and 1″ quoins dressing to exposed corners of basement	„	0 4 6	8,258	
4	Burnt stone slabs 6″ thick 2 lines dressed to exposed faces and 1 line dressing in other portions and fixing in lime mortar ..	S.ft.	0 6 0	2,411	
5	Burnt stone slabs 6″ thick roughly dressed and fixed in lime mortar in all walls at ground level for damp proof course with asphalt joints	„	0 4 0	1,675	
6	Sized stone in lime mortar 1 : 2 for superstructure including bond stones 6′ apart with neat clear joints and quoins dressing at all corners	C.ft.	0 5 0	9,542	
7	Burnt brick in lime mortar 9″ thick wall with ex-met at every 4th course laid in cement mortar well bonded on either side to main walls	„	0 7 0	270	
8	Teakwood doors $\frac{1}{3}$ panelled $\frac{2}{3}$ glazed 3″×5″ frame $1\frac{1}{2}$″ thick shutters with rectangular glazed fan light 2′ high including brass parliamentary hinges, bolts, hooks, etc., complete	S.ft.	1 10 0	570	
9	Teakwood windows 3″×5′ frame $1\frac{1}{4}$″ thick shutters fully glazed in four leaves including $\frac{3}{4}$′ Q iron bars and brass parliamentary hinges, bolts, hooks, etc., complete with rectangular glazed fan light 2′ high ..	Sqr.	1 12 0	896	
10	Pillars of size stone masonry in lime mortar $1\frac{1}{2}$′ square with neat clear joints for quoins dressing and white cement pointing complete	C.ft.	0 14 0	360	

No.	Items of work	Per	Rate	Quantity	Rate to be quoted
			Rs. a. p.		
11	Cut stone base and capital as per design including fixing in cement pointing, etc., complete	Set.	8 0 0	20	
12	Tata's listed rolled steel beams including hoisting and fixing and boxing with brick bats in cement mortar with necessary pipes, bolts and nuts and drilling holes, etc., complete	Cwt.	10 0 0	130.44	
13	Burnt stone slabs 8″ thick below girders 3 lines dressed at top and 1 line dressed at other faces including setting in lime mortar ..	S.ft.	0 8 0	105	
14	Roofing with reinforced cement concrete 1 : 2 : 4 interspersed with good burnt brick on edge as per design and specification to carry a total load intensity of 2 cwts., per S.ft., for a span of 12′ including smooth lime mortar plastering for ceiling with covering and including the cost of centering etc.	Sqr.	65 0 0	18.93	
15	Roofing :—Same as per item No. 14, but for a span of 9′	,,	60 0 0	19·60	
16	Roofing :—Same as per item No. 15, but in addition 3″ of surki concrete and 2 courses of flat tiles laid in lime mortar and ½″ smooth mortar plastering on top finished to necessary slope for drainage	,,	70 0 0	17·97	
17	Cut stone cornice as per drawing 2½′ projection and 9″ deep fixed in lime mortar including white cement pointing	R.ft.	3 0 0	54½	
18	Size stone in lime mortar (1 : 2) parapet wall 12″ thick and 2′ high as per drawing (modern type) including white cement pointing 2 lines dressing to coping slab, etc., complete	,,	1 12 0	177	
19	Providing and fixing C.I. railing as per design including 2 coats of approved paint and teakwood polished hand rail 4″×3″ for front verandah sides	,,	2 8 0	10	
20	Flooring with 1½″ cement concrete 1 : 2 : 4 on 3″ of lime concrete laid on 9″ of boulder and sand filling including finishing the top with ½″ cement plaster mixed with red oxide or any specified color with cut lines and rounding corners, etc., complete. ..	Sqr.	25 0 0	48·88	
21	Constructing teakwood stairs as per drawing, including teakwood newels as per design and ceiling planks ½″ thick below and 2 coats of varnishing, etc., complete ..	S.ft.	3 8 0	116	
22	Teakwood turned balustrated railing for stairs 2¾′ high with teakwood sill and hand rail including polishing with necessary fixtures, etc., complete	R.ft.	2 12 0	39	
23	Plastering with lime mortar 3 coats over stone work	Sqr.	3 8 0	64·83	
24	Plastering with lime mortar 2 coats on brick work	,,	3 0 0	6·60	
25	White washing 2 coats same as 22 and 23 ..	,,	0 4 0	71·43	
26	Silicate painting 2 coats	,,	3 0 0	23·42	
27	One line dressing the masonry outside facing in superstructure	,,	0 2 0	53·02	
28	White cement pointing including raking joints ½″ deep and cutting lines	,,	3 8 0	70·29	

No.	Items of work	Per	Rate	Quantity	Rate to be quoted
			Rs. a. p.		
	First Floor.				
1	Size stone in lime mortar 1 : 2 for superstructure including bond stones 6′ apart with neat clear joints and quoins dressing at all corners	C.ft.	0 5 6	7,067	
2	Burnt brick in lime mortar 4½″ thick wall with ex-met at every 4th course laid in cement mortar well bonded on either side into main walls	,,	0 7 6	135	
3	Burnt stone slabs 6″ thick 2 line dressed where exposed and 1 line dressed in other portions including setting in lime mortar ..	S.ft.	0 7 0	615	
4	Burnt stone slabs 8″ thick 3 line dressed at top and 1 line dressing in other portions laid in lime mortar	,,	0 9 0	66	
5	Teakwood door ⅓ panelled ⅔ glazed 3″×5″ frame 1½″ thick shutters with rectangular glazed fan light 2′ high including brass parliamentary hinges, bolts, hooks, etc. complete	,,	1 12 0	450	
6	Teakwood windows 3″×5″ frame 1¼″ thick shutters fully glazed in 4 leaves including ¾″ Q iron bars and brass parliamentary hinges, bolts, hooks etc., complete with rectangular glazed fan light 2′ high ..	,,	1 14 0	588	
7	Pillars of sized stone masonry in lime mortar 1½′ square and with neat clear joints and quoins dressing and white cement pointing, etc., complete	C.ft.	0 14 6	216	
8	Cut stone base and capital as per design including fixing cement pointing, etc., complete	Set	8 8 0	12	
9	Tata's tested rolled steel beams and joists including hoisting, fixing, boxing with brick bats in cement mortar	Cwt.	10 8 0	74.41	
10	Flooring with 1½″ cement concrete 1 : 2 : 4 on 3″ to 4½″ of surki concrete including finishing the top with ½″ cement plaster mixed with red oxide or any specified colour with cut lines and rounding corners, etc., complete	Sqr.	25 0 0	34.19	
11	Roofing with reinforced cement concrete 1 : 2 : 4 interspersed with good burnt bricks on edge as per design and specification to carry a total load of 1½ cwts., per s.ft., for a span of 12′ including smooth lime mortar plastering for ceiling below with covering including the cost of centering and on top 3″ of surki concrete and 2 courses of flat tiles laid in lime mortar and ½″ smooth lime mortar plastering finished	,,	80 0 0	20.34	
12	Roofing exactly similar to the item No. 11 but for a span of 9′	,,	75 0 0	18.65	
13	Sized stone in lime mortar 1 : 2 parapet wall 18″ high and 12″ thick as per drawing with fluted slabs over window openings and raised parapet in front including white cement pointing 2 line dressed coping slab, etc., complete	R.ft.	2 0 0	329	

No.	Items of work	Per	Rate	Quantity	Rate to be quoted
			Rs. a. p.		
14	Providing and fixing C.I. railing as per design including 2 coats of approved painting with teakwood polished hand rail 4″×3″ ..	R.ft.	2 12 0	70	
15	Plastering with lime mortar 3 coats over stone work	Sqr.	4 0 0	51.46	
16	Plastering with lime mortar 2 coats on brick walls	„	3 8 0	6.60	
17	White washing 2 coats same as item No. 15 and 16	„	0 4 6	57.06	
18	White cement pointing including raking joints ½″ deep and cutting lines	„	4 0 0	51.19	
19	Silicate painting 2 coats	„	3 8 0	15.70	
20	1 line dressing to masonry out side facing ..	S.ft.	0 2 0	458	

N. KRISHNAIENGAR,
Executive Engineer.

OFFICE OF THE EXECUTIVE ENGINEER, KRISHNARAJASAGAR DIVISION, KRISHNARAJASAGAR.

Notification dated 23rd September 1936.

SALE OF PORTABLE STEAM ENGINE 6 H.P.

Sealed tender for the purchase of the above engine will be received in this office up to 2 P.M., on the 20th October 1936.

The engine will be available for inspection in Hulikere Tunnel works near Byadarahalli Railway Station, Mysore Railways.

The tender should be accompanied with an earnest money of Rs. 50.

The earnest money should be sent either by money order or Insurance by Currency Notes.

The Executive Engineer reserves to himself the right to refuse the highest tender without assigning any reasons therefor.

The Deposit of the successful tenderer will be retained and he may remit the value of the engine within ten days from the date of acceptance of the tender and take delivery of the article.

If the full value is not remitted and taken delivery of the engine within the specified time, the successful tenderer will have to forfeit his earnest money and it will be credited to the Government.

Arrangements will be made to refund the earnest money of the unsuccessful tenderer as soon as possible after the tenders are opened and decided upon.

Notification dated 23rd September 1936.

The following amounts are outstanding under 17 (*a*) Public Works Deposits against the contractors noted below for the last one year. If the amount is not claimed within one month from this date, it will be credited to Government :—

		Rs. a. p.
May 1931	1. From raiyats of Lalanahalli village, being the contribution for constructing a Madavoi in IX Branch of Chamaraja Right Bank channel as per Comptroller's No. 290—WAD. 2, dated 26th August 1936	46 2 1
	2. From Mr. S. Srikantaiah for constructing a masonry head wall at 10—4 of Keggere Branch of Ramasamudram channel for want of heirship certificate	16 0 0
April 1930	3. Messrs. Abdul Hakh, Bangalore	3 6 0
January 1935	4. Mr. B. L. Ramakrishna Setty, Mysore	4 8 0
	5. „ Chikka Kala	0 5 0
	6. Mrs. Honni	0 14 0
	7. Mrs. Vishalakshamma	6 4 0
	8. Mr. Chikkanahalli Nanja	0 11 0